

August 30, 2013

KEITH B. JACKSON, P.E. LISA A. TROPEPE, P.E.

Allen P. Hubbard, P.E. Program Administrator NPDES Stormwater Section Florida Department of Environmental Protection Division of Water Resource Management

Palm Beach County Municipal Separate Storm Sewer System (MS4) Re:

NPDES Permit No. FLS00018 (Cycle 3)

Year 2 Annual Report Comments - Town of Manalapan

Engenuity Group Project No. 03005.01

Mr. Hubbard:

The following information is being submitted on behalf of the Town of Manalapan in response to the August 6, 2013 comment letter from the FDEP for NPDES Permit No. FLS000018:

## SWMP Inspection Schedule

All co-permittees shall meet the minimum inspection requirements detailed in Table II.A.1.a. of the MS4 permit. Town of Manalapan - Did not report illicit discharge inspections

The Town of Manalapan has 12 catch basins that are inspected at the beginning of each month. The inspections for illicit discharges, connections and dumping are completed in conjunction with the routine catch basin inspections. The Town also has 15,480 linear feet of swales that are completely inspected once every three years or 72 hours after a significant rainfall event, prior to hurricane watches or tropical depression to verify the proper functionality of the system. Similar to the catch basin, the inspections for the swale system for both routine and the illicit discharges are performed together.

If you should have any questions please do not hesitate to call.

Sincerely,

Lina Camacho, E.I.

Project Engineer

Cc:

Bob Donovan

Lisa Petersen

a Carrey w